

**SECTION 01070 - MAILBOX SUPPORTS**

*(Follow all instructions. If there are no instructions above a subsection, paragraph, sentence, or bullet, then include them in the project. The specifications may be modified to include project specific specifications, but all additions, deletions, or modifications must be sent to the ODOT Technical Resource and Senior Specifications Engineer for review and approval.)*

*(Use the following lead-in paragraph when subsections .00, .80, and .90 are NOT included in the project.)*

Comply with Section 01070 of the Standard Specifications.

*(Use the following lead-in paragraph and subsections .00, .80, and .90 when existing mailbox supports are reused. Use only when the existing mailbox supports, brackets, hardware, and post sockets are crash worthy and meet current standards. Check with the Designer.)*

Comply with Section 01070 of the Standard Specifications modified as follows:

~~*(Use the following subsection .00 when existing mailbox supports are reused. Use only when the existing mailbox supports, brackets, hardware, and post sockets are crash worthy and meet current standards. Check with the Designer.)*~~

**01070.00 Scope** - Add the following paragraph to the end of this subsection:

This work includes removing, maintaining, and reinstalling existing mailboxes and existing supports.

~~*(Use the following subsections .80 and .90 when existing mailbox supports are reused. Use only when the existing mailbox supports, brackets, hardware, and post sockets are crash worthy and meet current standards. Check with the Designer.)*~~

**01070.80 Measurement** - Add the following paragraph to the end of this subsection:

The quantities of mailboxes and supports removed, maintained, and reinstalled will be measured on the unit basis, regardless of type, installed in permanent locations.

**01070.90 Payment** - Add the following pay item:

Pay Item	Unit of Measurement
(d) Remove and Reinstall Mailbox Supports .....	Each

Item (d) includes removing mailboxes and supports, maintaining them at temporary locations, and reinstalling them at their permanent locations.