

SP00252 (2015 Specifications: ~~11-13-14~~[103-10-16](#))

*(Use this Section when the Contractor is to construct temporary work bridges or trestles for Contractor workers.)*

## SECTION 00252 - TEMPORARY WORK BRIDGES

*(Follow all instructions. If there are no instructions above a subsection, paragraph, sentence, or bullet, then include them in the project. The specifications may be modified to include project specific specifications, but all additions, deletions, or modifications must be sent to the ODOT Technical Resource and Senior Specifications Engineer for review and approval.)*

Section 00252, which is not a Standard Specification, is included in this Project by Special Provision.

### Description

**00252.00 Scope** - This work consists of designing (if applicable), constructing, maintaining, and removing temporary work bridges or trestles necessary to construct the new structure.

### Materials

**00252.10 Material** - Provide materials for temporary work bridges or trestles meeting the requirements of the applicable Sections of Part 00500.

### Construction

**00252.40 Construction** - Provide stamped working drawings and calculations of the work bridges or trestles according to 00150.35.

Design work bridges or trestles according to AASHTO "Guide Design Specifications for Bridge Temporary Works".

Construct work bridges or trestles at the locations shown and according to AASHTO "Construction Hand Book for Bridge Temporary Works".

Construct the work bridges or trestles so they satisfy all the requirements of applicable permitting agencies.

### Maintenance

**00252.60 Maintenance** - Maintain work bridges or trestles in a safe and functional condition.

Provide and place suitable approved barriers on or near the work bridges or trestles to prevent public access.

### Finishing and Cleaning Up

**00252.70 Structure Removal** - When the temporary work bridges or trestles are no longer needed, remove them according to Section 00310.

Satisfy all requirements of applicable permitting agencies during work bridge or trestle removal.

Restore all areas occupied by the work bridges or trestles to original condition.

#### **Measurement**

**00252.80 Measurement** - No measurement of quantities will be made for work performed under this Section.

#### **Payment**

**00252.90 Payment** - The accepted quantities of work performed under this Section will be paid for at the Contract lump sum amount for the item "Temporary Work Bridges".

Payment will be payment in full for furnishing and placing all materials, and for furnishing all equipment, labor, and incidentals necessary to complete the work as specified.

~~Progress payments and retained amounts will be made according to 00195.50 except for the following:~~

- ~~• No payment will be made for materials on hand.~~
- ~~• 20 percent of the bid amount will be retained until satisfactory removal of the work bridges is done.~~

No separate or additional payment will be made for designing, constructing, maintaining, and removing temporary work bridges ~~or trestles~~.